No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	II. Putting up new pukka stalls on the site of the old domestic basin demonstration shed.				
1	Dismantling existing roof and carting to Stores	Sqr.		20·20	
2	Teakwood wrought and put up	C.ft.		90	
3	Roofing with corrogated asbestos sheet roofing, complete	Sqr.		25·84	
4	Providing iron brackets with bolts and nuts, etc., complete, including fixing	Cwt.		4	
5	Flooring with 1½" cement concrete over 3" ordinary jelly concrete and cement plaster mixed with red colour and cut to tile pattern ..	Sqr.		12·30	
	III. Improving in fine arts section by removing arch ways.				
1	Providing and fixing R. S. joists for lintels over openings	Cwt.		48	
2	Dismantling brick masonry in arch ways ..	C.ft.		856	
3	Chunam plastering smooth sides of opening dismantled	Sqr.		10·22	
4	Providing and fixing cement fret work for ventilators	S.ft.		258	
5	Providing and fixing glasses outside to prevent rain water	,,		258	

N.B.—The above quantities are for blocks in the exhibition premises and are not guaranteed. The distribution will be made among different contractors for speedy execution of work.

S. RAMASWAMY,
Assistant Engineer.

SHIMOGA FOREST DIVISION.

Notification dated 1st May 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M., on 15th May 1935, for restoring Udagani Herekere, Reg. No. 1138, Shikarpur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited Rs. 150 (one hundred and fifty only) as earnest money, and be superscribed "Tender for restoring Udagani Herekere, Reg. No. 1138, Shikarpur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures, and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Work should be according to Departmental specification.

14. Transfer of works to other parties or subletting of contracts is prohibited.

15. Monthly progress should not be less than Rs. 500 and should be completed by the end of October 1935.

16. Cement and C. I. pipes will be supplied by the Department and the cost with centage recovered.

Abstract estimate for restoring Udagani Hirekere, Register No. 1138, Shikarpur Taluk.

Sl. No.	Items of work	Unit	Quantity	Rate	
				In Figures	In words
	Bund to R. L. 50.00, top width 6 ft. slopes front 3 : 1 and rear 2 : 1.				
1	Clearing jungle and roots, etc.	grades	15		
2	Cutting grips or picking 3″ depth	C.yds.	308		
3	Earthwork to bund including watching and consolidation complete	,,	2,424		
4	Earthwork re-using soil available from Draft and approach clearing	,,	355		
5	Gravelling the top of bund	,,	165		
6	Turfing slopes	Sqr.	288.36		
7	Providing and fixing grade stones on concrete bed including painting, etc., with bed slabs..	Each	17		
8	Providing and fixing Index stones	,,	17		
9	Providing and fixing B. M. stones	,,	2		
10	Reg. No. and date stones	,,	1		
	Constructing Sluice at R. L. 44.00.				
1	Earthwork cut opening the bund and refilling with consolidation	C.yds.	71		
2	Extra earth for filling	,,	20		
3	Earthwork excavation for foundation ..	,,	7		
4	Stone jelly concrete in cement mortar 1 : 6 : 10 .	C.ft.	194		
5	Stone jelly concrete in cement mortar 1 : 6 ..	,,	285		
6	Cement concrete coping over head walls ..	,,	4½		
7	Providing and fixing burnt stone slabs 6″ thick..	S.ft.	21		
8	Providing and fixing C. I. pipes 6″ diameter including cart-hire and fixing etc., complete..	R.ft.	30		
9	Cement plastering ½″ thick	Sqr.	0.50		
10	Cement pointing exposed faces	,,	1.50		
11	Providing and fixing teak wood plug and iron rod with locking arrangements	Each	1		
12	Cutting holes in slabs	,,	3		
13	R. S. revetment in front of sluice	C.yds.	11		
	Constructing Waste Weir 80 ft. long with one 6″ pipe diameter at R. L. 47.00.				
1	Earth work excavation for foundation ..	C.yds.	44		
2	Stone jelly concrete in cement mortar 1 : 6 : 10	C.ft.	337		

Sl. No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
3	Size stone in cement mortar 1 : 6	C.ft.	655		
4	Cement concrete coping	,,	45		
5	Rough stone work, new	C.yd.	58		
6	Draft and approach clearing	,,	355		
7	Fixing C. I. pipe 6″ diameter at R.L. 47.00 including cart hire etc., complete	R.ft.	24		
8	Masonry work for fixing pipe, size stone in cement mortar 1 : 6	..	Lump sum		
9	Unforseen works	..	do		

B. KRISHNA RAO,
Executive Engineer.

KADUR DIVISION.

Notification.

In inviting the attention of the public to notification dated 24th March 1935, calling for tenders for the Construction of Sri Ganapathi Temple at Chikmagalur, they are hereby informed that the date for receiving the tender is extended up to 20th May 1935.

L. A. H. WINCKLER,
Executive Engineer.

MEDICAL DEPARTMENT

VICTORIA HOSPITAL, BANGALORE.

Tender Notice dated 4th May 1935.

1. Notice is hereby given that sealed tenders in triplicate on half sheet foolscap size paper will be received at the Office of the Victoria Hospital, Bangalore, by the undersigned at 11 A.M., on Friday the 24th May 1935, for the supply of articles of Bedding and Clothing required for the use of the said Hospital.

2. No tenders will be received after the date and hour abovementioned.

3. Tenders to be superscribed " Tender for the supply of Bedding and Clothing to the Victoria Hospital."

4. No tender will be received unless accompanied by a deposit of Rs. 100 in Cash or Currency Notes or Treasury Receipts.

5. Tenders will be opened by the Medical Officer in charge, at his office in the Victoria Hospital, on the date and at the hour abovementioned in the presence of such tenderers, as may choose to attend.

6. The rate of each item must be specified in figures as well as in words and they must be for the particular kind or brand of the articles as specified in the list appended hereto. The value of each tender must be worked out according to the rates tendered and the total value must also be entered in words in ink. Tenders, not confirming to this rule, will be rejected.

7. The quantities stated in the list are not guaranteed.

8. The Senior Surgeon does not bind himself to accept the lowest or any other tender or to assign any reason for not accepting any tender. He may also accept one or more items in any one tender without accepting the other item or items.

9. The deposit of the successful tenderer will be returned after the whole quantity of linen is supplied. The linen should be supplied within a month from the date of receiving intimation of the acceptance of his tender.

10. No advance of cash will be made to the contractor; payment will be made as early as possible on his producing the necessary bill for the whole quantity supplied.

11. In case the contractor fails to comply with the order given to him, he shall forfeit the deposit money to Government and also be bound to make good to Government any loss which may arise from such cessation.